

Proposal with Expansion FECHA: 14 de Agosto de 2025 FECHA DE VENCIMIENTO: 29 de Agosto de 2025

Folio No # 20250269

Alexander

Tel:

Email:

Cant.	Concepto	Precio	Total
42	SOLAR PANEL 600 W ~ 615 W MONOCRYSTALLINE BIFACIAL		
1	HUAWEI SUN2000-20KTL-M3		
42	NOVOTEGRA MOUNTING SYSTEM, ANODIZED ALUMINUM		
1	BOS		
1	STRUCTURE FOR SOLAR PANELS AND CONCRETE BASES		
1	INCREASE IN CONTRACTED DEMAND WITH CFE		
1	PROCESSING PROCEDURES FOR CFE INTERCONNECTION		
1	CONSUMPTION MONITORING WITH ZERO EXPORT		
1	EPDM GASKETS		
1	ENGINEERING, LOGISTICS AND INSTALLATION		

Subtotal \$ 466,735.90

IVA \$ 74,677.74

TOTAL (MXN) \$ 541,413.64

Total \$541,413.64 MXN VAT included

Medium Voltage Solar Panel Installation Project Details

1. Photovoltaic Equipment:

- 42 monocrystalline solar panels, 600W~615W, with a 25-year warranty. (Subject to availability; bifacial, Longi, Jinko, Canadian, Trina, or JA)
- 1 central inverter, 20KW, with a 10-year warranty. (Subject to availability; Growatt, Huawei, or Solis)
- WiFi antenna and system monitoring for remote management and monitoring. (Includes Zero Export)

2. Structure and Mounting:

- NOVOTEGRA brand mounting accessories, made of anodized aluminum:
 - 4.72 m aluminum rail
 - Middle clamp, end clamp
 - L-foot, T-polts, top clips, N3
 - Ground and electrical connections
- Solar panel structure (Design approved), (6013 welding, 2 coats of anti-corrosion paint, 2 coats of oil paint (you can choose the color)
- Concrete bases with chemical anchoring to the slab, 3"x1.5" PTR, galvanized steel, designed to withstand strong



winds.

3. Cabling and Protection:

- Heavy-duty THHW solar cable.
- Electrical protection.
- ABB watertight enclosures and load center with overlay.
- MC4 connectors, black UV-resistant plastic straps.

4. Services included:

- Labor, equipment shipping, and engineering.
- Complete management of the CFE grid interconnection contract under the Net Energy Metering (Net Metering) scheme.
- One free preventive maintenance session.

5. IMPORTANT:

- The cost of the bidirectional meter is not included; this is subject to CFE equipment availability. For more information, consult your sales advisor.
- On-site electrical adjustments are not included, if necessary.

6. Payment Method:

- 70% down payment.
- The remaining 20% is due upon completion and delivery to the site. Construction time is 30 days.
- 10% for CFE interconnection processing.
- We accept credit card payments.

7. Tax Information:

- Company Name: Energía y Construcción Ecológica del Caribe S.A. de C.V.
 - RFC: ECE231213Q84
 - Billing email: facturacion@solardelsureste.com.mx
 - Bank accounts:
 - BBVA Pesos:
 - CLABE: 012180001223946939
 - Account: 0122394693
 - BBVA USD:
 - CLABE USD: 012180001223951694
 - Account USD: 0122395169
- VAT included.