

COSTOS - SSFV 25.42 kWp - FLORES VALADEZ MA DE LA LUZ								
Panel								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
1	Trina Solar N-type i-TOPCon bifacial dual glass...	Pza	41	84.3	3,457.1	1,577.4	64,673.0	64,673.0
Adicionales								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
2	2. Flete de Paneles Solares (ej. GDL a León/Mo...	Pza	41	9.9	404.7	184.5	7,564.5	121,008.2
3	4. Flete Inversor Central (ej. GDL a León/Moro...	Pza	1	85.6	85.6	1,600.0	1,600.0	
4	5. Garantía del inversor a 10 años (5 años e...	Pza	1	282.6	282.6	5,281.4	5,281.4	
5	6.1. Cable FV + MC4 - Inv. Central	Pza	41	8.9	365.2	166.5	6,825.7	
6	7.1. Protecciones CD -Inv. Central	Pza	41	7.0	285.2	130.0	5,330.0	
7	13.1. Material Eléctrico - Inv. Central (GDMTO)	Pza	41	31.8	1,305.0	595.0	24,393.4	
8	21.2. Gestoría CFE - Media Tensión (GDMTO & G...	Pza	1	267.5	267.5	5,000.0	5,000.0	
9	22. UVIE - Trámite CFE - Media tensión	Pza	1	428.0	428.0	8,000.0	8,000.0	
10	23. UIIE - Trámite CFE - Media tensión	Pza	1	1,444.5	1,444.5	27,000.0	27,000.0	
11	24. Comisión venta ** 7% del subtotal **	Pza	1	1,209.8	1,209.8	22,613.6	22,613.6	
12	26. Seguro de paneles solares ** 2% del subtot...	Pza	1	395.9	395.9	7,399.7	7,399.7	
Inversor								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
13	Growatt Inverter 25 kW	Pza	1	2,258.6	2,258.6	42,251.1	42,251.1	42,251.1
Estructura								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
14	8.2. Estructura de Aluminio - C/Angulo	Pza	41	73.0	2,991.9	1,364.0	55,924.0	60,176.5
15	9.2. Tornillería - c/ angulo	Pza	41	2.8	114.7	52.3	2,143.1	
16	10. Impermeabilizante	Pza	41	2.8	112.9	51.5	2,109.5	
Mano de obra								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
17	15. M.D.O. para Instalación de paneles	Pza	41	45.5	1,864.5	850.0	34,850.0	38,950.0
18	16. M.D.O. para Adecuaciones eléctricas para l...	Pza	41	5.4	219.4	100.0	4,100.0	
					17,492.9		327,058.9	327,058.9

\$379,388.4	CTO	\$327,058.9	81.8%
\$464,000.0	VTA	\$400,000.0	100%
\$84,611.6	UTIL	\$72,941.1	18.2%
CON IVA		SIN IVA	