

COSTOS - SSFV 2.48 kWp - SANCHEZ VAZQUEZ MELISSA								
Panel								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
1	Trina Solar N-type i-TOPCon bifacial dual glass...	Pza	4	84.3	337.3	1,552.1	6,208.3	6,208.3
Adicionales								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
2	2. Flete de Paneles Solares (ej. GDL a León/Mo...	Pza	4	13.4	53.4	246.0	984.0	13,338.6
3	4. Flete Inversor Central (ej. GDL a León/Moro...	Pza	1	38.0	38.0	700.0	700.0	
4	6.1. Cable FV + MC4 - Inv. Central	Pza	4	9.0	36.2	166.5	665.9	
5	7.1. Protecciones CD -Inv. Central	Pza	4	7.1	28.2	130.0	520.0	
6	13.1. Material Eléctrico - Inv. Central (Resid...	Pza	4	31.6	126.6	582.8	2,331.1	
7	21.1. Gestoría CFE - Residencial & Baja tensi?...	Pza	1	162.9	162.9	3,000.0	3,000.0	
8	24. Comisión venta ** 7% del subtotal **	Pza	1	162.9	162.9	3,000.8	3,000.8	
9	26. Seguro de paneles solares ** 2% del subtot...	Pza	1	47.3	47.3	870.6	870.6	
10	5. Garantía del inversor a 10 años (5 años e...	Pza	1	68.8	68.8	1,266.2	1,266.2	
Inversor								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
11	Solis Inverter 3K S6-GR1P3K-S	Pza	1	550.3	550.3	10,129.7	10,129.7	10,129.7
Estructura								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
12	8.2. Estructura de Aluminio - C/Angulo	Pza	4	74.1	296.3	1,364.0	5,456.0	5,870.9
13	9.2. Tornillería - c/ angulo	Pza	4	2.8	11.4	52.3	209.1	
14	10. Impermeabilizante	Pza	4	2.8	11.2	51.5	205.8	
Mano de obra								
Partida	Material	Unidad	Cantidad	Costo Unit	Subtotal	Costo Unit	Subtotal	
15	15. M.D.O. para Instalación de paneles	Pza	4	46.2	184.6	850.0	3,400.0	3,400.0
					2,115.3		38,947.5	38,947.5

\$45,179.1	CTO	\$38,947.5	82.2%
\$54,984.0	VTA	\$47,400.0	100%
\$9,804.9	UTIL	\$8,452.5	17.8%
CON IVA		SIN IVA	